



Republic of the Philippines
SOUTHERN LUZON STATE UNIVERSITY
Lucban, Quezon

REQUEST FOR QUOTATION

**RENOVATION/IMPROVEMENT OF LICUP COVERED COURT AT SLSU TIAONG CAMPUS
(TIAONG)**

Purchase Request No. 2023-05-1340
Approved Budget for the Contract: ₱ 329,886.00


The Southern Luzon State University through the Bids and Awards Committee invites interested firms/supplier to submit quotation for the procurement for **Renovation/Improvement of LICUP Covered Court at SLSU Tiaong Campus (Tiaong)** to apply the sum of **Three Hundred Twenty-Nine Thousand and Eight Hundred Eighty-Six Pesos Only (₱ 329,886.00) inclusive of VAT**, being the **Approved Budget for the Contract (ABC)**, details as follows:

Qty.	Unit	ITEM/S DESCRIPTION
1	lot	Renovation/ Improvement of Licup Covered Court at SLSU Tiaong Campus

1. The quotation must be submitted (can also be send thru email at the contact details listed below) or to the Office of the Procurement Office/Bids and Awards Committee, Southern Luzon State University, 2nd Flr. Hermano Puli Building, and shall be received by the Committee.

E-mail : slsuprocedurement2021@gmail.com

2. The SLSU reserves the right to reject any or all quotations and/or proposals and waive any formalities/ informalities therein and to accept such bids it may consider as most advantageous to the agency and to the government. Southern Luzon State University SLSU neither assumes any obligation for whatsoever losses that may be incurred in the preparation of bids, nor does it guarantee that an award will be made.


Samuel T. Sacopla
Head, Procurement office *2023*
Southern Luzon State University
Lucban, Quezon
Tel. No.: (042)540-6519



Republic of the Philippines
SOUTHERN LUZON STATE UNIVERSITY
Lucban, Quezon

REQUEST FOR QUOTATION

Office/End-User: SLSU Tiaong		Date:
COMPANY NAME:		PR No.: 2023-05-1340
ADDRESS :		
TEL. NO./FAX NO. :		TIN No.:

Please quote your lowest price on the item(s) listed below, subject to the Terms & Conditions stated below and submit your quotation duly signed by your representative not later than _____ of _____ in the return envelope attached herewith to the Procurement office.

TERMS and CONDITIONS

1. All entries must be typewritten or legibility written.
2. Delivery period within _____ upon conforme of the approved Purchase Order (P.O).
Administrative penalties to Sec. 69 of the Revised IRR-RA 1984 shall be imposed for non-delivery without valid reason.
3. Warranty shall be for a minimum of three (3) months for Supplies & Materials;
(1) one year for Equipment from date of acceptance by the end-user.
4. Price validity shall be for a period of sixty (60) calendar days.
5. Suppliers required to submit updated documents yearly such as G-EPS Resgistration, Certificate of Tax, Mayor's Permit, DTI, Bank Name/Account and Branch for evaluation of the Procurement Office upon submission of the quotation.
6. Bidders shall submit complete specifications showing products certification, if applicable.
7. Please indicate the brand for each items being offered.
8. The Approved budget celling for this procurement is PHP 329,886.00.


SAMUEL T. SACOPLA
 Head, Procurement Office *2023*

Item #	Qty.	Unit	ITEM/S DESCRIPTION	Unit Price	Total Cost
	1	lot	Renovation/ Improvement of Licup Covered Court at SLSU Tiaong Campus		

Source of Fund:	Warranty:
Delivery Period:	Price Validity:

After having carefully need & accepted your Genaral Conditions, We quote you on the item(s) at prices note above. If the space of providcec on the Delivery Period, Warranty & Price Validity are left blank, It means that I concur w/ the Terms & Conditions specified by SLSU Procurement Office.

Printed Name/Signature/Date



REPUBLIC OF THE PHILIPPINES
SOUTHERN LUZON STATE UNIVERSITY
PHYSICAL PLANT AND FACILITIES



PROJECT TITLE:	Renovation/ Improvement of Licup Covered Court at SLSU Tiaong Campus			
PROJECT LOCATION:	SLSU Tiaong Campus, Tiaong, Quezon			
OWNER:	Southern Luzon State University			
MODE OF IMPLEMENTATION:	by Contract			
DURATION:	25 working days for 3 Mason, 1 Equipment Operator, 2 Helpers & 2 Painters			
SUMMARY				
ITEM	DESCRIPTION	MATERIALS COST	LABOR AND EQUIPMENT COST	TOTAL COST
1	Mobilization & Demobilization			
2	Demolition			
3	Earthworks			
4	Concreting Works			
5	Formworks			
TOTAL ESTIMATED DIRECT COST				
OVERHEAD, CONTINGENCIES AND MISC. (OCM)				
CONTRACTOR'S PROFIT				
VALUE ADDED TAX (VAT)				
TOTAL ESTIMATED PROJECT COST				-

REPUBLIC OF THE PHILIPPINES
SOUTHERN LUZON STATE UNIVERSITY
PHYSICAL PLANT AND FACILITIES

PROJECT TITLE:	Renovation/ Improvement of Licup Covered Court at SLSU Tiaong Campus
PROJECT LOCATION:	SLSU Tiaong Campus, Tiaong, Quezon
OWNER:	Southern Luzon State University
MODE OF IMPLEMENTATION:	by Contract
DURATION:	25 working days for 3 Mason, 1 Equipment Operator, 2 Helpers & 2 Painters

BILL OF MATERIALS

ITEM	DESCRIPTION	Qty	Unit	Direct Cost	Total Materials Cost
I. Concreting Works 2500psi (25.96m3)					
1	Portland Cement		bags		-
2	Sand (S1)		m3		-
3	Gravel (G1)		m3		-
3	Deformed bars 10mm dia.		pcs		-
4	G.I. Tie Wire #16		kgs		-
SUB-TOTAL					-
II. Formworks					
1	Coco Lumber 2"x2"x12'		pcs		-
2	Phenolic Board 1/2"		pcs		-
3	Assorted Nails (#1,#2,#3,#4)		kgs		-
					-
III. Painting Works					
1	Elastomeric Waterproofing, Cool Water		tins		-
2	Elastomeric Waterproofing, Asian Green		tins		-
3	Skim Coat		bags		-
4	Rubberized Floor Coating Chlorinated Rubber Base Top Coat (White)		gal		-
5	Rubberized Floor Coating Chlorinated Rubber Base Top Coat (Reducer)		gal		-
5	Sanding Paper #60		sq. ft		-
6	Paint Roller #4		pcs		-
7	Paint Brush 2"		pcs		-
					-



Project: Renovation/ Improvement of Licup Covered Court at SLSU Tiaong Campus

Location: SLSU Tiaong Campus, Tiaong, Quezon

Implementation: by Contract

Duration: 25 working days for 3 Mason, 1 Equipment Operator, 2 Helpers & 2 Painters

SCOPE OF WORKS

I. Demolition

- Demolition of existing Slab on Grade and Stage.
- Contractor must be responsible for their own equipment

II. Earthworks

- After demolition and clearing of existing slab on grade. The base should be **compacted** firmly.
- Use of Mini Compactor is advised.

III. Concreting Works

- Concreting of the new slab on grade and the stage shall be based on a **2500PSI (1:2.5:5)** mixture.
- This includes laying of new rebars of 10mm dia. Spaced at 400mm O.C. both ways as provided in the estimate and
- The contractor must provide at least 3 Mason & 2 Helpers.
- Use of bagger mixer and a concrete vibrator are recommended.
- A 28 days compressive strength test of concrete shall be provided.

IV. Painting Works

- The contractor must provide at least 2 painters to repaint the covered court including the column and the existing stage.

PREPARED BY:

RONELITO O. SAN JOSE, PME
Head, Physical Plant and Facilities

REVIEWED BY:

ENGR. MELVIN A. MAKIPAGAY
Director, Planning and Development Office
(Infrastructure)

RECOMMENDING APPROVAL:

DR. FREDERICK T. VILLA
VP, Administration and Financial Affairs

APPROVED BY:

DR. DORACIE B. ZOLETA-NANTES
University President