



Republic of the Philippines
SOUTHERN LUZON STATE UNIVERSITY
Lucban, Quezon

REQUEST FOR QUOTATION

PROFESSIONAL FEE FOR STRUCTURAL INVESTIGATION (PDO-INFRA)

Purchase Request No. 2024-10-2183

Approved Budget for the Contract: ₱ 708,000.00


The Southern Luzon State University through the Bids and Awards Committee invites interested firms/supplier to submit quotation for the procurement of **Professional Fee for Structural Investigation (PDO-Infra)** to apply the sum of **Seven Hundred Eight Thousand Pesos Only (₱ 708,000.00)** inclusive of VAT, being the **Approved Budget for the Contract (ABC)**, details as follows:

Qty.	Unit	ITEM/S DESCRIPTION
1	lot	Professional fee for Structural Investigation Level 2 of Design and Innovation Bldg. at SLSU Lucena
1	lot	Professional fee for Structural Investigation Level 2 of Physical and Natural Sciences Bldg. at SLSU Lucena
		*see attached document for specifications

1. The quotation must be submitted (can also be send thru email at the contact details listed below) or to the Office of the Procurement Office/Bids and Awards Committee, Southern Luzon State University, 2nd Flr. Hermano Puli Building, and shall be received by the Committee.

E-mail : slsuprourement@slsu.edu.ph

2. The SLSU reserves the right to reject any or all quotations and/or proposals and waive any formalities/ informalities therein and to accept such bids it may consider as most advantageous to the agency and to the government. Southern Luzon State University SLSU neither assumes any obligation for whatsoever losses that may be incurred in the preparation of bids, nor does it guarantee that an award will be made.


MARIDEL C. ZABELLA
Head, Procurement Office
Southern Luzon State University
Lucban, Quezon
Tel. No.: (042)540-6519

Republic of the Philippines
SOUTHERN LUZON STATE UNIVERSITY
Planning and Development Office
Lucban , Quezon

PROJECT TITLE: PROFESSIONAL FEE FOR STRUCTURAL INVESTIGATION LEVEL 2 OF DESIGN AND INNOVATION BLDG.

PROJECT LOCATION: SLSU LUCENA CAMPUS, LUCENA, QUEZON

OWNER : Southern Luzon State University

ABC : P 420,000.00

MODE OF IMPLEMENTATION : by Contract

PROJECT DURATION: 60 Calendar Days (Except Sundays)

SUMMARY

ITEM	QTY.	UNIT	DESCRIPTION	UNIT COST	TOTAL
I	1	lot	Research and Data Gathering		
II	1	lot	Actual Site Visit and Inspection		
III	1	lot	Gathering of Structural Specimen for Laboratory Testing		
IV	1	lot	Mark-ups of Damages and Defects		
V	1	lot	Evaluation and Interpretation of Test Results		
VI	1	lot	Preparation & Submission of Results and Recommendations (signed and sealed by a registered Structural Engineer)		
				TOTAL ESTIMATED DIRECT COST	P
				OVERHEAD, CONTINGENCIES & MISC.(OCM)	P
				INDIRECT COST	P
				CONTRACTOR'S PROFIT	P
				VALUE ADDED TAX (VAT)	P
				TOTAL PROJECT COST	P

TOTAL PROJECT COST IN WORDS: _____

CONTRACTOR / BIDDER : _____



Republic of the Philippines
Southern Luzon State University
Project Management Office
Lucban, Quezon

PROJECT TITLE : Professional Fee for Structural Investigation Level 2 of Design and Innovation Bldg.
at

SLSU Lucena

PROJECT LOCATION : SLSU Lucena Campus, Lucena City, Quezon


OWNER : Southern Luzon State University

PROJECT DURATION : 60 CD (Except Sundays)


SCOPE OF WORKS

1. Initial assessment and data gathering must be conducted by the consultant. (History, change in occupancy, renovations and other factors)
2. The consultant must conduct an ocular site inspection of the building. The photographs and locations of the physical defects such as cracks, reinforcement corrosion, noticeable beam deflections, and other visual defects should be recorded and identified.
3. Non-destructive testing like concrete testing and steel testing should be performed and concrete samples or specimens should be collected on-site and be taken to the laboratory for analysis.
4. The consultant should prepare a key plan of defects found during the site inspection. The damages and defects found during the visual inspection should be marked on the plans in detail.
5. Upon summarizing the results and findings, the assigned professional should itemize and break down these findings and come up with the conclusion of the overall safety of the structure.
6. The assigned professional will prepare recommendations based on the conclusion and defects that have been found on the site.
7. The deliverables of the project will include:
 - a. A comprehensive investigation report detailing:
 - i. Observations and findings
 - ii. Causes of defects or damage
 - iii. Recommendations for repairs or strengthening
 - iv. Prioritized repair schedule
 - b. Supporting documents:
 - i. Photographs and videos
 - ii. Test results and laboratory reports
 - iii. Structural Analysis and Calculations

Prepared by:


Engr. Mary Rose N. Bojelador
Asst. Planning Engineer

Approved by:


Engr. Melvin A. Makipagay
Director – Project Management Office

Republic of the Philippines
SOUTHERN LUZON STATE UNIVERSITY
Planning and Development Office
Lucban , Quezon

PROJECT TITLE: PROFESSIONAL FEE FOR STRUCTURAL INVESTIGATION LEVEL 2 OF PHYSICAL AND NATURAL SCIENCES

PROJECT LOCATION: SLSU LUCENA CAMPUS, LUCENA, QUEZON

OWNER : Southern Luzon State University

ABC : P 288,000.00

MODE OF IMPLEMENTATION : by Contract

PROJECT DURATION: 60 Calendar Days (Except Sundays)

SUMMARY

ITEM	QTY.	UNIT	DESCRIPTION	UNIT COST	TOTAL
I	1	lot	Research and Data Gathering		
II	1	lot	Actual Site Visit and Inspection		
III	1	lot	Gathering of Structural Specimen for Laboratory Testing		
IV	1	lot	Mark-ups of Damages and Defects		
V	1	lot	Evaluation and Interpretation of Test Results		
VI	1	lot	Preparation & Submission of Results and Recommendations (signed and sealed by a registered Structural Engineer)		
				TOTAL ESTIMATED DIRECT COST	P
				OVERHEAD, CONTINGENCIES & MISC.(OCM)	P
				CONTRACTOR'S PROFIT	P
				VALUE ADDED TAX (VAT)	P
				TOTAL PROJECT COST	P

TOTAL PROJECT COST IN WORDS: _____

CONTRACTOR / BIDDER : _____



Republic of the Philippines
Southern Luzon State University
Project Management Office
Lucban, Quezon

PROJECT TITLE : Professional Fee for Structural Investigation Level 2 of Physical and Natural Sciences Bldg. at SLSU Lucena

PROJECT LOCATION : SLSU Lucena Campus, Lucena, Quezon


OWNER : Southern Luzon State University

PROJECT DURATION : 60 CD (Except Sundays)

SCOPE OF WORKS

1. Initial assessment and data gathering must be conducted by the consultant. (History, change in occupancy, renovations and other factors)
2. The consultant must conduct an ocular site inspection of the building. The photographs and locations of the physical defects such as cracks, reinforcement corrosion, noticeable beam deflections, and other visual defects should be recorded and identified.
3. Non-destructive testing like concrete testing and steel testing should be performed and concrete samples or specimens should be collected on-site and be taken to the laboratory for analysis.
4. The consultant should prepare a key plan of defects found during the site inspection. The damages and defects found during the visual inspection should be marked on the plans in detail.
5. Upon summarizing the results and findings, the assigned professional should itemize and break down these findings and come up with the conclusion of the overall safety of the structure.
6. The assigned professional will prepare recommendations based on the conclusion and defects that have been found on the site.
7. The deliverables of the project will include:
 - a. A comprehensive investigation report detailing:
 - i. Observations and findings
 - ii. Causes of defects or damage
 - iii. Recommendations for repairs or strengthening
 - iv. Prioritized repair schedule
 - b. Supporting documents:
 - i. Photographs and videos
 - ii. Test results and laboratory reports
 - iii. Structural Analysis and Calculations

Prepared by:


Engr. Mary Rose N. Bojelador
Asst. Planning Engineer

Approved by:


Engr. Melvin A. Makibagay
Director – Project Management Office