



Republic of the Philippines  
**SOUTHERN LUZON STATE UNIVERSITY**  
Lucban, Quezon



## REQUEST FOR QUOTATION

### ACU REPLACEMENT FOR HOTEL (BAO)

Purchase Request No. 2025-03-0980

Approved Budget for the Contract: ₱ 78,326.50

The Southern Luzon State University through the Bids and Awards Committee invites interested firms/supplier to submit quotation for the procurement for **ACU Replacement for Hotel (BAO)** to apply the sum of **Seventy-Eight Thousand Three Hundred Twenty-Six Pesos and Fifty Centavos Only ₱ 78,326.50** inclusive of VAT, being the **Approved Budget for the Contract (ABC)**, details as follows:

Qty.	Unit	ITEM/S DESCRIPTION
2	set	1.5 HP Split-type Wall Mounted ACU, Inverter, R-32A, w/ installation
2	set	Safety Breaker w/ Housing 2P-30amp
100	m	THHN Electrical Wire 5.5mm2
20	pcs	1/2" Ø Orange PVC Pipe x 3m.
60	pcs	Metal Clamp 1/2"


1. The quotation must be submitted (can also be send thru email at the contact details listed below) or to the Office of the Procurement Office/Bids and Awards Committee, Southern Luzon State University, 2<sup>nd</sup> Flr. Hermano Puli Building, and shall be received by the Committee.

E-mail : [slsuprourement@slsu.edu.ph](mailto:slsuprourement@slsu.edu.ph)

2. The SLSU reserves the right to reject any or all quotations and/or proposals and waive any formalities/ informalities therein and to accept such bids it may consider as most advantageous to the agency and to the government. Southern Luzon State University SLSU neither assumes any obligation for whatsoever losses that may be incurred in the preparation of bids, nor does it guarantee that an award will be made.

  
**MARIDEL C. ZABELLA**  
Director, Procurement Office  
Southern Luzon State University  
Lucban, Quezon  
Tel. No.: (042)540-6519





1.5HP Inverter Split Type Aircon |

REPUBLIC OF THE PHILIPPINES  
SOUTHERN LUZON STATE UNIVERSITY  
GENERAL SERVICES OFFICE

PROJECT TITLE:	ACU REPLACEMENT FOR HOTEL ROOM 2 and 8					
PROJECT LOCATION:	SLSU Main Campus					
OWNER:	SLSU					
MODE OF IMPLEMENTATION:	by contract					
DURATION:						
<b>SUMMARY</b>						
ITEM	DESCRIPTION	TOTAL MATERIALS DIRECT COST	LABOR & EQUIPMENT COST	MATERIALS UNIT COST		TOTAL
1	ACU					
<b>TOTAL ESTIMATED PROJECT COST</b>						

PREPARED BY:

ENGR. RONELITO O. SAN JOSE

Director, General Services

REVIEWED BY:

DR. ARVIN N. NATIVIDAD

VP-Administrative and Financial Affairs

APPROVED BY:

DR. FREDERICK T. VILLA

University President

REPUBLIC OF THE PHILIPPINES  
SOUTHERN LUZON STATE UNIVERSITY  
GENERAL SERVICES OFFICE

PROJECT TITLE:	ACU REPLACEMENT FOR HOTEL ROOM 2 and 8						
PROJECT LOCATION:	SLSU Main Campus						
OWNER:	SLSU						
MODE OF IMPLEMENTATION:	by contract						
DURATION:							
<b>BILL OF MATERIALS</b>							
ITEM	DESCRIPTION	QTY	UNIT	Materials Direct Cost	Total Materials Direct Cost	Labor & Equipment Cost	TOTAL UNIT COST
<b>I. ACU</b>							
1	1.5H HP Split-type Wall Mounted ACU, Inverter, R-32A, w/installation	2	sets				
2	Safety Breaker w/ Housing 2P-30amp	2	sets				
3	THHN Electrical Wire 5.5 mm <sup>2</sup>	100	m				
4	1/2" Ø Orange PVC Pipe x 3m.	20	pcs				
5	Metal Clamp 1/2"	60	pcs				
<b>SUB-TOTAL</b>							

**Republic of the Philippines  
Southern Luzon State University  
General Services Office  
Lucban, Quezon**

**PROJECT TITLE:** ACU REPLACEMENT FOR BRC HOTEL ROOM 2 AND 8

**PROJECT LOCATION:** SLSU Main Campus

**OWNER:** Southern Luzon State University

**SUBJECT:** Scope of works/General Works

**SCOPE OF WORKS**

**II. Supply and Installation**

- b. The contractor shall demolish, supply, deliver, install, test and set to work the ACUs in the location indicated in the purchase order.

**GENERAL WORKS**

- 8. The contractor shall furnish all the materials, equipments, tools, apparatus, appliances, accessories, transportation, labor and supervision required for the completion of the project.
- 9. All contractors submitting proposal for this project shall first examine the site.
- 10. All works must execute strictly in accordance with current practices.
- 11. The contractor shall provide the bracket needed for the outdoor unit of the ACU.
- 12. The contractor shall cut necessary wall and floor openings for pipe/duct penetrations and embedments.
- 13. The Contractor shall be responsible for verifying location, position and sizing of power supply and connections.
- 14. The contractor shall demolish existing ductworks, pipe works, conduits, cables and other accessories not necessary for the rehabilitation works.

Prepared by:

**ENGR. RONELITO O. SAN JOSE**  
Director, General Services

Recommending approval by:

**DR. ARVIN N. NATIVIDAD**  
VP-Administrative and Financial Affairs

Approved by:

**DR. FREDERICK T. VILLA**  
University President



Southern Luzon State University  
General Services Office

## CERTIFICATION

This is to certify that the procurement of 2 set split-type Air Conditioning Unit (ACU) with the cooling capacity of 4,026 kJ/hr and 1.5 Hp respectively, requested by Dr. Claire Ann M. Yao PhD to be installed as new unit in Room 2 and 8, Hotel Building, SLSU Main Campus complied with the basic requirements for installation of ACUs, such as;

For both types of Unit:

1. Correct capacity of ACU for Cooling load,
2. Available source and correct size of power supply line
3. Strength of wall to hold the indoor unit,
4. Proper spacing between wall and indoor unit,
5. Appropriate installation height from ground,
6. Correct tilt angle of indoor unit,

For Split-type Units:

7. Correct location of outdoor unit,
8. Proper placement of outdoor unit, and
9. Right distance between indoor and outdoor unit.

Note: Need additional extension of 12-gauge wire from the source and 20 Amps, single phase, double-pole circuit breaker for each split-type units.

This certification is issued this 31th day of January 2025 upon the request of the end-user as a requirement for procurement of the said equipment.

Certified by:

**ENGR. RONELITO O. SAN JOSE**  
Director, General Services Office